

FORM 6

I.D.No. _____

Borehole Number: MWM-2D
 Surface Elevation (Ft./MSL): 1708.80' (ft)
 Borehole Diameter: 12 1/4" inches, From 0.0' To 50.0'
7 7/8" inches, From 50.0' To 167.0'
 Total Depth: 167.0' (ft)
 Depth to Static Ground Water Level (SWL): 113.5' (ft)
 Date SWL Measured: 10/16/91 (mm/dd/yy)

Drilling Method: AIR ROTARY-TRI-CONE ROLLER BIT
 Date Drilled: 10/9/90 - 10/16/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: PCM
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water Observations	Samples No. Rec'd Att	Comments	Well/Piezometer Construction	Depth (Ft)
0	MINE SPOIL-MEDIUM STIFF, GRAY TO GRAY BROWN, CLAYEY SILT, SHALE FRAGMENTS, COAL FRAGMENTS				DAMP		0
5							5
10							10
15							15
20							20
25					DAMP		25
30							30
35							35
40							40
44.0'							
45	SOFT, GRAY, CLAYSTONE				TOP OF ROCK 44.0' BONEY COAL FRAGMENTS DRY		45
50							50
52.0'					INSTALLED 8" STEEL CASING TO 50.0' STOPPED TO ALLOW GROUT TO SET		50
55	SOFT, GRAY, SANDY SHALE, WEATHERED						55
57.0'							55
SEE NEXT PAGE							
60							60

* ▽ Encountered Ground Water ▼ Composite Static Water Level

**Recovered/Attempted

F-256

SLW 4/30/91 (3)

Use additional sheets with this format as necessary