

FORM 6

I.D.No. _____

Borehole Number: TB-5
 Surface Elevation (Ft/MSL): 1721.34' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 62.0'
3 1/2" Inches, From 62.0' To 201.0'
 Total Depth: 201.0' (ft)
 Depth to Static Ground Water Level (SWL): 73.2' (ft)
 Date SWL Measured: 12/19/89 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 11/14/89 - 11/19/89 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (ft)	Lithologic Description	Plot	Ground Water Observations	Samples No.	Sec. 18 Alt.	Comments	Well/Piezometer Construction	Depth (ft)
180	HARD, GRAY, COARSE GRAINED SANDSTONE, SLIGHTLY BROKEN TO UNBROKEN, COAL STREAKS			13	10.0' / 10.0'			180
185								185
190	MEDIUM HARD, GRAY, SANDY CLAYSTONE, WITH COAL STREAKS, BROKEN			14	10.0' / 10.0'	190.6' TO 190.7' COAL STRINGER		190
195	COAL					MERCER COAL		195
200	MEDIUM HARD, GRAY SHALE, BROKEN			15	7.0' / 7.0'	SUCKENSIDES		200
205	BOTTOM OF BORING 201.0'						BORING TREMIE GROUTED WITH CEMENT/BENTONITE MIXTURE UPON COMPLETION OF BEDROCK PRESSURE TESTING	205
210								210
215								215
220								220
225								225
230								230
235								235
240								240

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted

F-256
 SLW 2/15/91

Use additional sheets in this format as necessary