

FORM 6

I.D.No. _____

Borehole Number: MWK-1U
 Surface Elevation (Ft/MSL): 1787.84' (ft)
 Borehole Diameter: 12 1/4" inches, From 0.0' To 65.0'
7 7/8" inches, From 65.0' To 260.0'
 Total Depth: 260.0' (ft)
 Depth to Static Ground Water Level (SWL): 98.0' (ft)
 Date SWL Measured: 10/26/90 (mm/dd/yy)

Drilling Method: AIR ROTARY-TRI-CONE ROLLER BIT
 Date Drilled: 10/23/90 - 10/26/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: PCM
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (ft)	Uthologic Description	Plot	Ground Water Observations	Sample No.	Sample Description	Comments	Well/Piezometer Construction	Depth (ft)
0	MINE SPOIL-DARK GRAY TO GRAY, SILTY CLAY, DARK GRAY, CARBONACEOUS SHALE FRAGMENTS, GRAY SANDSTONE FRAGMENTS, WOOD FRAGMENTS					DAMP		0
5								5
10						MOIST		10
15								15
20								20
25						MOIST		25
30								30
35								35
40	40.0'					TOP OF ROCK 40.0'		40
45	SOFT, GRAY SHALE, WEATHERED					WATER AT SPOIL ROCK INTERFACE		45
50								50
55								55
60								60

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted

F-256

SLW 4/16/91 (1)

Use additional sheets with this format as necessary