

FORM 6

I.D.No. _____

Borehole Number: CB-3
 Surface Elevation (Ft/MSL): 1697.98' (ft)
 Borehole Diameter: 3 7/8" inches, From 0.0' To 45.0'
 — inches, From — To —
 Total Depth: 45.0' (ft)
 Depth to Static Ground Water Level (SWL): — (ft)
 Date SWL Measured: — (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX CORE
 Date Drilled: 3/14/91 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: RHB
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (ft)	Uthologic Description	Plot	Ground Water Observations	Sample No.	Sample Rec'd At	Comments	Well/Piezometer Construction	Depth (ft)
0	MINE SPOIL—MEDIUM STIFF, BROWN, GRAY, CLAYEY SILT AND SHALE FRAGMENTS, SLIGHTLY WEATHERED—DAMP TO MOIST							0
5								5
10								10
15								15
20								20
25								25
30	30.2'							30
35	SOFT TO MEDIUM HARD, MEDIUM TO DARK GRAY CLAYSTONE, SLIGHTLY BROKEN TO UNBROKEN 38.3'			1	4.65' / 4.8'	30' PIECE OF TIRE STUCK IN CORE BARREL 30.1' WOOD FRAGMENTS GRADING TO SOME FINE SAND AT 34.1'		35
40	VERY HARD, MEDIUM GRAY TO GRAY SANDSTONE, TRACE CLAYSTONE, SLIGHTLY BROKEN TO UNBROKEN 45.0'			2	9.7' / 10.0'	38.7' TRACE CLAYSTONE		40
45	BOTTOM OF BORING 45.0'					BORING TREMIE GROUTED TO SURFACE UPON COMPLETION USING A CEMENT/BENTONITE MIXTURE		45
50								50
55								55
60								60

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted