

FORM 6

I.D.No. _____

Borehole Number: CB-4
 Surface Elevation (Ft./MSL): 1715.35' (ft)
 Borehole Diameter: 3 7/8 inches, From 0.0' To 45.0'
— inches, From — To —
 Total Depth: 45.0' (ft)
 Depth to Static Ground Water Level (SWL): — (ft)
 Date SWL Measured: — (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX CORE
 Date Drilled: 3/14/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: RHB
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water [*] Observations	Samples No. <u>1</u> <u>2</u>	Comments	Well/Piezometer Construction	Depth (Ft)
0	MINE SPOIL—MEDIUM STIFF, BROWN, GRAY CLAYEY SILT AND SHALE FRAGMENTS, SLIGHTLY WEATHERED—DAMP TO MOIST						0
5							5
10							10
15							15
20							20
25							25
30							30
35	35.0' SOFT TO MEDIUM HARD, MEDIUM TO DARK GRAY CLAYSTONE, SLIGHTLY BROKEN TO UNBROKEN 39.5'			1 4.0'/5.0'	HIT BOULDER 35.0' TOP OF ROCK		35
40	VERY HARD, MEDIUM GRAY TO GRAY SANDSTONE, SLIGHTLY BROKEN TO UNBROKEN 45.0'			2 10.0'/10.0'	IRON STAINING AT 38.5'		40
45	BOTTOM OF BORING 45.0'						45
50							50
55							55
60							60

* ∇ Encountered Ground Water ∇ Composite Static Water Level

** Recovered/Attempted

F-256

SLW 4/30/91 ①

Use additional sheets with this format as necessary