

FORM 6

I.D.No. _____

Borehole Number: CB-1
 Surface Elevation (Ft/MSL): 1716.76' (ft)
 Borehole Diameter: 3 7/8" inches, From 0.0' To 72.5'
 — inches, From — To —
 Total Depth: 72.5' (ft)
 Depth to Static Ground Water Level (SWL): — (ft)
 Date SWL Measured: — (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX CORE
 Date Drilled: 3/11/91 - 3/12/91 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: RHB
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Uthologic Description	Plot	Ground Water Observations	Samples No. Rec'd At	Comments	Well/Piezometer Construction	Depth (Ft)
0	MINE SPOIL—SOFT, BROWN TO GRAY, CLAYEY SILT AND ROCK FRAGMENTS, SOME FINE SAND —DAMP TO MOIST						0
5							5
10							10
15							15
20					HIT BOULDER AT 22' AUGERED THROUGH		20
25							25
30							30
35							35
40							40
45							45
50	58.5' SOFT TO MEDIUM HARD, MEDIUM TO DARK GRAY CLAYSTONE, UNBROKEN TO BROKEN, GRADING TO SILTY CLAYSTONE AT 61'			1	SANDSTONE BOULDER AND SHALE FRAGMENTS AND SILTY CLAY AUGERED TO 56' SHALE AND COAL FRAGMENTS AND SILTY CLAY SPUT SPOON SAMPLE FROM 56.5' TO 57.1' 58.5' TOP OF ROCK		50
55				1			55
60				1			60

* ▽ Encountered Ground Water ▽ Composite Static Water Level

**Recovered/Attempted

F-256

SLW 4/23/91

Use additional sheets with this format as necessary