

FORM 6

I.D.No. _____

Borehole Number: TB-7
 Surface Elevation (Ft/MSL): 1616.15' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 14.0'
3 1/2" Inches, From 14.0' To 149.0'
 Total Depth: 149.0' (ft)
 Depth to Static Ground Water Level (SWL): 43.4' (ft)
 Date SWL Measured: 1/30/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 1/29/90 - 1/30/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Driller's License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (ft)	Lithologic Description	Plot	Ground Water Observations	Samples No.	Bar #s	Comments	Well/Piezometer Construction	Depth (ft)
60	MEDIUM HARD, GRAY -BROWN SANDY SHALE, SLIGHTLY BROKEN TO UNBROKEN			6	10.0' / 10.0'			60 -
65	MEDIUM HARD, GRAY CLAYSTONE, SLIGHTLY BROKEN TO UNBROKEN			7	10.0' / 10.0'	IRON STAINING		65 -
70	MEDIUM HARD, GRAY -BROWN, FINE TO MEDIUM GRAINED SANDSTONE WITH SHALE STREAKS			8	10.0' / 10.0'	79.0' TO 79.4' COAL SEAM 80.0' TO 80.4' COAL SEAM		70 -
75				9	10.0' / 10.0'			75 -
80	SOFT, BLACK COAL			10	10.0' / 10.0'			80 -
85	MEDIUM HARD, GRAY CLAYSTONE, SLIGHTLY BROKEN TO UNBROKEN			11	10.0' / 10.0'			85 -
90	MEDIUM HARD, GRAY -BROWN SHALE, CARBONACEOUS, SLIGHTLY BROKEN TO UNBROKEN							90 -
95	MEDIUM HARD, GRAY CLAYSTONE							95 -
100	MEDIUM HARD, GRAY -BROWN SHALE, SLIGHTLY BROKEN TO UNBROKEN					IRON STAINING		100 -
105								105 -
110								110 -
115	SEE NEXT PAGE					IRON STAINING		115 -
120								120 -

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted

F-256

SLW- 2/15/91

Use additional sheets with this format as necessary