

FORM 6

I.D.No. _____

Borehole Number: TB-8
 Surface Elevation (Ft/MSL): 1694.35' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 40.0'
3 1/2" Inches, From 40.0' To 174.0'
 Total Depth: 174.0' (ft)
 Depth to Static Ground Water Level (SWL): 59.2' (ft)
 Date SWL Measured: 1/23/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 1/22/90 - 1/23/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water Observations	Sample No.	Rec'd At	Comments	Well/Piezometer Construction	Depth (Ft)
120	MEDIUM HARD, GRAY, FINE TO MEDIUM GRAINED SANDSTONE, CARBONACEOUS, WITH SHALE STREAKS			9	10.0' / 10.0'	128.0' TO 128.2' CLAY SEAM		120
125								125
130								130
135				10	10.0' / 10.0'	133.3' TO 133.4' SHALE RIP-UP CLASTS 133.6' TO 133.9' SHALE RIP-UP CLASTS		135
140								140
145				11	10.0' / 10.0'			145
150								150
155				12	10.0' / 10.0'			155
160								160
165				13	10.0' / 10.0'			165
170								170
175				14	5.0' / 5.0'	HAD WATER CIRCULATION TO BOTTOM OF HOLE 174.0'		175
180								180
	BOTTOM OF BORING 174.0'						BORING TREMIE GROUTED TO SURFACE USING CEMENT/BENTONITE MIXTURE	

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted

F-256
 SLW 2/15/91

Use additional sheets with this format as necessary