

FORM 6

I.D.No. _____

Borehole Number: TB-10
 Surface Elevation (Ft/MSL): 1698.52' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 40.5'
3 1/2" Inches, From 40.5' To 189.0'
 Total Depth: 189.0' (ft)
 Depth to Static Ground Water Level (SWL): 49.0' (ft)
 Date SWL Measured: 1/19/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 1/17/90 - 1/19/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water* Observations	Samples No. Back to Top	Comments	Well/Piezometer Construction	Depth (Ft)
120	MEDIUM HARD, GRAY, FINE TO MEDIUM GRAINED SANDSTONE, WITH SHALE STREAKS, CARBONACEOUS, SLIGHTLY BROKEN TO UNBROKEN, MASSIVE			9	10.0' / 10.0'		120
125							125
130				10	10.0' / 10.0'		130
135							135
140				11	10.0' / 10.0'	NO IRON STAINS ON OPEN FRACTURES	140
145							145
150	MEDIUM HARD, GRAY, SANDY CLAYSTONE			12	10.0' / 10.0'		150
155	MEDIUM HARD, GRAY, FINE TO MEDIUM GRAINED SANDSTONE, CARBONACEOUS, SHALE STREAKS, SLIGHTLY BROKEN TO UNBROKEN						155
160				13	10.0' / 10.0'		160
165							165
170				14	10.0' / 10.0'		170
175							175
180	MEDIUM HARD, GRAY, SANDY CLAYSTONE, VERY BROKEN					176.3" TO 176.4" COAL STRINGER	180

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted