

FORM 6

I.D.No. _____

Borehole Number: TB-10
 Surface Elevation (Ft/MSL): 1698.52' (ft)
 Borehole Diameter: 6" inches, From 0.0' To 40.5'
3 1/2" inches, From 40.5' To 189.0'
 Total Depth: 189.0' (ft)
 Depth to Static Ground Water Level (SWL): 49.0' (ft)
 Date SWL Measured: 1/19/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 1/17/90 - 1/19/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water Observations	Samples		Comments	Well/Piezometer Construction	Depth (Ft)
				No.	Depth (Ft)			
180	MEDIUM HARD, GRAY, SANDY CLAYSTONE, VERY BROKEN 183.4'					182.0' TO 182.3' COAL SEAM		180
185	MEDIUM HARD, GRAY, FINE TO MEDIUM GRAINED SANDSTONE, SLIGHTLY BROKEN TO UNBROKEN, MASSIVE 189.0'			15	10.0' 10.0'			185
190	BOTTOM OF BORING 189.0'						BORING TREMIE GROUTED WITH CEMENT/BENTONITE MIXTURE UPON COMPLETION OF BEDROCK PRESSURE TESTING	190
195								195
200								200
205								205
210								210
215								215
220								220
225								225
230								230
235								235
240								240

* ☒ Encountered Ground Water☒ Composite Static Water Level

**Recovered/Attempted

F-256

SLW 2/15/91

Use additional sheets with this format as necessary