

FORM 6

I.D.No. _____

Borehole Number: TB-29
 Surface Elevation (Ft/MSL): 1829.77' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 9.0'
3 1/2" Inches, From 9.0' To 219.0'
 Total Depth: 219.0' (ft)
 Depth to Static Ground Water Level (SWL): 160.0' (ft)
 Date SWL Measured: 1/25/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 1/24/90 - 1/25/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: M.J.G.
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water Observations	Samples No.	Recovery %	Comments	Well/Plazometer Construction	Depth (Ft)
60	MEDIUM HARD, GRAY -BROWN, SANDY SHALE, WEATHERED, BROKEN TO VERY BROKEN							60
65	MEDIUM HARD, BLACK COAL			6	10.0'/10.0'			65
70	MEDIUM HARD, GRAY CLAYSTONE, SLIGHTLY BROKEN TO UNBROKEN							70
75	MEDIUM HARD, GRAY -BROWN, SANDY CLAYSTONE, UNBROKEN TO BROKEN			7	10.0'/10.0'	IRON STAINING		75
80	MEDIUM HARD, GRAY -BROWN SHALE, UNBROKEN TO SLIGHTLY BROKEN							80
85				8	10.0'/10.0'			85
90								90
95				9	10.0'/10.0'	FRACTURES WITH IRON STAINING		95
100								100
105				10	10.0'/10.0'			105
110								110
115	MEDIUM HARD, GRAY, FINE TO MEDIUM GRAINED SANDSTONE WITH SHALE STREAKS, CARBONACEOUS, SLIGHTLY BROKEN TO UNBROKEN			11	10.0'/10.0'			115
120								120

* ☒ Encountered Ground Water ☒ Composite Static Water Level

** Recovered/Attempted

F-256

SLW 2/15/91

Use additional sheets with this format as necessary