

FORM 6

I.D.No. _____

Borehole Number: TB-25
 Surface Elevation (Ft/MSL): 1703.59' (ft)
 Borehole Diameter: 3 1/4" ID inches, From 0.0' To 29.0'
3 1/2" inches, From 29.0' To 79.0'
 Total Depth: 79.0' (ft)
 Depth to Static Ground Water Level (SWL): 26.0' (ft)
 Date SWL Measured: 2/12/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 2/9/90 - 2/12/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water* Observations	Samples		Comments	Well/Piezometer Construction	Depth (Ft)
				No.	Discs At			
60	MEDIUM HARD, GRAY, FINE TO MEDIUM GRAINED SANDSTONE WITH SHALE STREAKS, SLIGHTLY BROKEN TO UNBROKEN			4	10.0'	70.0' BECOMES GRAY 70.0' TO 70.4' FRACTURE HEAVY IRON STAIN		60
65					10.0'			65
70				5	10.0'			70
75					10.0'			75
79.0'								
80	BOTTOM OF BORING 79.0'						BORING TREMIE GROUTED TO SURFACE USING CEMENT/BENTONITE MIXTURE	80
85								85
90								90
95								95
100								100
105								105
110								110
115								115
120								120

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted

F-256
SLW 2/13/91

Use additional sheets with this format as necessary