

FORM 6

I.D.No. _____

Borehole Number: TB-28
 Surface Elevation (Ft/MSL): 1718.64' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 48.0'
3 1/2" Inches, From 48.0' To 99.0'
 Total Depth: 99.0' (ft)
 Depth to Static Ground Water Level (SWL): 68.9' (ft)
 Date SWL Measured: 1/17/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINEDate Drilled: 1/16/90 - 1/17/90 (mm/dd/yy)Drilled By: HETAGER DRILLING CO.Drillers License Number: 1728Logged By: MJGCounty: JEFFERSON COUNTYTownship or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water * Observations	Samples No.	Sample Depth (Ft)	Comments	Well/Piezometer Construction	Depth (Ft)
60	MEDIUM HARD, GRAY-BROWN, INTERBEDDED SHALE AND FINE TO MEDIUM GRAINED SANDSTONE, TRACE BLACK CARBONACEOUS STREAKS, UNBROKEN TO SLIGHTLY BROKEN			2	10.0' / 10.0'			60
65								65
70								70
75				3	10.0' / 10.0'			75
80						78.7' TO 84.4' HEAVY IRON STAIN		80
85				4	10.0' / 10.0'	85.0' TO 85.5' COAL STREAK 85.5' TO 85.6' COAL SEAM		85
90						88.6' COAL SPAR		90
95				5	10.0' / 10.0'			95
99.0'								
100	BOTTOM OF BORING 99.0'						BORING TREMIE GROUTED WITH CEMENT/BENTONITE MIXTURE UPON COMPLETION OF BEDROCK PRESSURE TESTING	100
105								105
110								110
115								115
120								120

* Encountered Ground Water Composite Static Water Level

**Recovered/Attempted

F-256

SLW 2/15/91

Use additional sheets with this format as necessary