

FORM 6

I.D.No. _____

Borehole Number: TB-27
 Surface Elevation (Ft/MSL): 1714.71' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 49.0'
3 1/2" Inches, From 49.0' To 99.0'
 Total Depth: 99.0' (ft)
 Depth to Static Ground Water Level (SWL): 5.0' (ft)
 Date SWL Measured: 1/12/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 1/11/90 - 1/12/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Driller's License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (ft)	Lithologic Description	Plot	Ground Water Observations	Sample No.	Sample Depth (ft)	Comments	Well/Piezometer Construction	Depth (ft)
0	(MINE SPOIL)—SOFT TO STIFF, GRAY-BROWN CLAYEY SILT AND SHALE FRAGMENTS, CARBONACEOUS, TRACE OF SANDSTONE FRAGMENTS			1	16/18	DRY-MOIST		0
5			▽	2	10/18			5
10				3	12/18			10
15				4	8/18			15
20				5	14/18			20
25				6	16/18			25
30				7	10/18			30
35				8	13/18	DRY-MOIST		35
40				9	18/18			40
45				10	18/18			45
49.0'				11	5/12			49.0'
50	MEDIUM HARD, GRAY BROWN, INTERBEDDED SHALE AND FINE GRAINED SANDSTONE			1	10.0'/10.0'	IRON STAIN		50
55								55
60								60

* ▽ Encountered Ground Water ▽ Composite Static Water Level

**Recovered/Attempted

F-256
SLW 2/15/91

Use additional sheets with this format as necessary

(2)