

FORM 6

I.D.No. _____

Borehole Number: TB-27
 Surface Elevation (Ft/MSL): 1714.71' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 49.0'
3 1/2" Inches, From 49.0' To 99.0'
 Total Depth: 99.0' (ft)
 Depth to Static Ground Water Level (SWL): 5.0' (ft)
 Date SWL Measured: 1/12/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 1/11/90 - 1/12/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water* Observations	Samples No. 10.0' 10.0' 10.0' 10.0'	Comments	Well/Piezometer Construction	Depth (Ft)
60	SEE PREVIOUS PAGE						60
61.0'	MEDIUM HARD, GRAY -BROWN, FINE TO MEDIUM GRAINED SANDSTONE, BROKEN TO UNBROKEN, TRACE CARBONACEOUS SHALE STREAKS			2	10.0' / 10.0'		65
65							70
70				3	10.0' / 10.0'		75
75							80
80					79.8' TO 79.9' COAL SEAM		85
85				4	10.0' / 10.0'		90
90							95
95	MEDIUM HARD, GRAY SHALE, SLIGHTLY BROKEN TO UNBROKEN			5	10.0' / 10.0'		100
96.0'							105
99.0'	BOTTOM OF BORING 99.0'					BORING TREMIE GROUTED WITH CEMENT/BENTONITE MIXTURE UPON COMPLETION OF BEDROCK PRESSURE TESTING	110
100							115
105							120
110							
115							
120							

* ☒ Encountered Ground Water☒ Composite Static Water Level

**Recovered/Attempted

F-256

SLW 2/15/91

Use additional sheets with this format as necessary