

FORM 6

I.D.No. _____

Borehole Number: TB-23
 Surface Elevation (Ft/MSL): 1717.29' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 40.0'
3 1/2" Inches, From 40.0' To 89.0'
 Total Depth: 89.0' (ft)
 Depth to Static Ground Water Level (SWL): 41.6' (ft)
 Date SWL Measured: 1/11/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 1/11/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: M.J.G.
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (ft)	Uthologic Description	Plot	Ground Water Observations	Samples No. Depth At	Comments	Well/Piezometer Construction	Depth (ft)
60	MEDIUM HARD, GRAY, FINE TO MEDIUM GRAINED SANDSTONE, UNBROKEN TO SLIGHTLY BROKEN, SHALE STREAKS			3	10.0' / 10.0'		60
65				4	10.0' / 10.0'		65
70					IRON STAIN ON OPEN FRACTURES 70.3' TO 70.5' HEAVY IRON STAIN		70
75				5	10.0' / 10.0'		75
80	BOTTOM OF BORING 89.0'			6	5.0' / 5.0'		80
85							85
90						BORING TREMIE GROUTED WITH CEMENT/BENTONITE MIXTURE UPON COMPLETION OF BEDROCK PRESSURE TESTING	90
95							95
100							100
105							105
110							110
115							115
120							120

* ▽ Encountered Ground Water ▽ Composite Static Water Level

**Recovered/Attempted

F-256
 SLW 2/15/91

Use additional sheets with this format as necessary