

FORM 6

I.D.No. _____

Borehole Number: TB-22
 Surface Elevation (Ft/MSL): 1733.78' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 60.0'
3 1/2" Inches, From 60.0' To 114.0'
 Total Depth: 114.0' (ft)
 Depth to Static Ground Water Level (SWL): 93.8' (ft)
 Date SWL Measured: 1/11/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 1/9/90 - 1/11/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Driller's License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water # Observations	Samples No. Rec'd	Comments	Well/Piezometer Construction	Depth (Ft)
60	SOFT, GRAY CLAYSTONE, WEATHERED			1	4.0' / 4.0'		60
65	MEDIUM HARD, GRAY, INTERBEDDED SHALE AND FINE GRAINED SANDSTONE, UNBROKEN TO SLIGHTLY BROKEN			2	10.0' / 10.0'		65
70							70
75				3	10.0' / 10.0'		75
80							80
85				4	10.0' / 10.0'		85
90							90
95	MEDIUM HARD, GRAY, FINE GRAINED SANDSTONE, SLIGHTLY BROKEN TO UNBROKEN, TRACE BLACK CARBONACEOUS STREAKS, SLIGHTLY WEATHERED		▽	5	10.0' / 10.0'		95
100							100
105				6	10.0' / 10.0'	103.4' TO 103.5' COAL STRINGER 105.1' TO 105.2' COAL STRINGER IRON STAINED	105
110	MEDIUM HARD, GRAY SHALE, SLIGHTLY BROKEN TO UNBROKEN, MASSIVE						110
115	BOTTOM OF BORING 114.0'					BORING TREMIE GROUTED WITH CEMENT/BENTONITE MIXTURE UPON COMPLETION OF BEDROCK PRESSURE TESTING	115
120							120

* ▽ Encountered Ground Water ▽ Composite Static Water Level

**Recovered/Attempted

F-256

SLW 2/15/91

Use additional sheets with this format as necessary