


LEGEND

- PROPERTY LINE
- PROPOSED 2FT CONTOUR
- PROPOSED 10FT CONTOUR



NARDONE BROTHER BAKING
COMPANY
D.B. 2724, PG. 466

CAVANAUGH ELECTRICAL
CONTRACTING, INC.
D.B. 2724, PG. 466

LUZERNE COUNTY INDUSTRIAL
DEVELOPMENT AUTHORITY
D.B. 2144, PG. 536

ROCCO DOMIANO
D.B. 1971, PG. 331

ROCCO DOMIANO
D.B. 1971, PG. 331

ROCCO DOMIANO
D.B. 1971, PG. 331

PROPOSED BUILDING PAD
297,575 SQ. FT.
ELEV=716.00


PROPOSED BUILDING PAD
374,000 SQ. FT.
ELEV=722.00

BASIN "B"

BASIN "A"

PIPE SCHEDULE						
PIPE	SIZE (IN)	TYPE	UPPER INVERT ELEVATION	LOWER INVERT ELEVATION	LENGTH (FT)	SLOPE
P-1	18	SLCPP	675.50	674.00	50	3.00%
P-2	18	SLCPP	676.00	672.00	105	3.81%
P-3	36	SLCPP	682.00	680.00	270	0.74%
P-4	24	SLCPP	707.00	690.00	167	10.18%
P-5	30	SLCPP	701.00	698.00	125	2.33%
P-6	24	SLCPP	693.75	687.00	81	8.33%
P-7	24	SLCPP	699.09	693.95	257	2.00%
P-8	24	SLCPP	703.15	699.29	257	1.50%
P-9	24	SLCPP	706.26	703.35	233	1.25%
P-10	24	SLCPP	708.69	706.46	203	1.10%
P-11	15	SLCPP	679.00	672.00	260	2.69%
P-12	24	SLCPP	669.90	669.03	125	0.70%
P-13	15	SLCPP	685.90	682.01	134	2.90%

STORM STRUCTURE SCHEDULE						
STRUCTURE	RIM ELEV.	PIPE NO.	IN INVERT	IN PIPE NO.	OUT INVERT	OUT REMARKS
I-1	705.90	P-7	693.95	P-6	693.75	TYPE M INLET
I-2	707.50	P-8	699.29	P-7	699.09	TYPE M INLET
I-3	707.50	P-9	703.35	P-8	703.15	TYPE M INLET
I-4	707.85	P-10	706.46	P-9	706.26	TYPE M INLET
I-5	712.80	-	-	P-10	708.69	TYPE M INLET
I-6	683.00	-	-	P-11	679.25	TYPE M INLET



Northeast Pennsylvania

613 Baltimore Drive
Suite 300
Wilkes-Barre, PA 18702-7903

Voice: 570-821-1999
Fax: 570-821-1990

Lehigh Valley

3893 Adler Place
Suite 100
Bethlehem, PA 18017

Voice: 484-821-0470
Fax: 484-821-0474

REVISIONS

SITE GRADING AND DRAINAGE PLAN

EARTH CONSERVANCY HUBER III
RECLAMATION PROJECT

HANOVER TOWNSHIP

LUZERNE COUNTY

PENNSYLVANIA

PROJECT NO. 2005-1748-02
DRAWING NO.

2 of 10